

| Customer: ben fyber | Job Ref: 43 |
|-------------------------------------|--------------------|
| Site: | Estimator: |
| House Ref: | Plot No(s): |
| | |
| Stair Type: Single Winder Staircase | Rise: 200 |
| Storey Height: 2600mm | Going: 222.12mm |
| Stair Width: 900mm | Pitch: 42° |
| Flight Length: 0 | |

COMPONENTS LIST

Cut Bot Riser 184mm Tread Width = 243mm

| Item | Туре | Finish Material | Qty | Lgth | Section | |
|------------------------------|------------|--------------------|-----|-------------|-------------|--|
| 1 No Single Winder Staircase | | | | | | |
| Assembly Require | ed | | 1 | | | |
| String | Straight | 32mm Redwood Pine1 | | AS DRAWINGS | | |
| | | (Furniture Grade) | | | | |
| Tread | Straight | 22mm MDF | 9 | 860 | 22 x 243 | |
| Tread | Winder | 22mm MDF | 1 | | AS DRAWINGS | |
| Riser | Straight | 9mm MDF | 11 | 857 | 9 x 206 | |
| Riser | Winder | 9mm MDF | 2 | 1220 | 9 x 206 | |
| Nosing | Half Round | 22mm MDF | 1 | 860 | 22 x 75 | |
| Newel Standard | Single | | 1 | 2400 | 90 x 90 | |
| Strings : Grade) | | | | | | |

x Newel Caps : Grade)

Please note

1) Labour MUST not be booked until the staircase is delivered.

2) Your staircase will be put into production within 24 hrs of placing this order and will be produced according to this drawing.

| Express Group Holdings | Inspection Record | | | |
|---|-----------------------------|--|--|--|
| INSPECTION SIGNATURES AND DATES | | | | |
| 1. Materials/Machining Checked by: | 2. Treatment Checked by: | | | |
| Date: | Date: | | | |
| 3. Pre-Assembly Checked by: | 4. Paint/Finish Checked by: | | | |
| Date: | Date: | | | |
| 5. Final Inspection Check and Comments: | | | | |
| Date: | | | | |
| BWF-Stair Labels Used: | Delivery Note No: | | | |
| Date: | | | | |